Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Invoice

From:
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

Invoice Number	INV-3383
Invoice Date	10th December 2025
Due Date	10th December 2025
Total Due	**£737.64**

To:
Amy Bradley
11 Thornhill Drive, Nuneaton, CV11 6TD
amymaybradley@hotmail.co.uk

Quotation for works at 11 Thornhill Drive as follows -

To address observations 1, 2, 5, 6, 8, 9, 10, 11, 14 and 15.

De-commissioning and removal of the existing consumer unit.

Supply and installation of an 18th edition regulations, metal clad consumer unit with RCD (Residual Current Device) and SPD (Surge Protection) as required to comply with BSEN7671 and Part P of the building regulations. This will be populated with circuit breakers for each circuit to create adequate circuit segregation.

Supply and Installation of 100A isolation switch to allow the whole installation to be isolated without the need to remove the main fuse.

Supply and installation of replacement supply tails of 25mm CSA as required.

Supply and installation of replacement main earth cable of 16mm CSA as required.

Supply and installation of replacement bonding cable to incoming water supply pipe cable of 10mm CSS as required.

Supply and installation of replacement bonding cable to incoming gas supply pipe cable of 10mm CSS as required.

A full test of the electrical installation will also be carried out as part of this piece of work and certification as required to comply with Part P of the building regulation including notification to your local authority.

Thanks for choosing Hiskins Electrical Services | Commercial & Domestic Electricians
Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Invoice

To address observation 4.

1 hour of investigation to establish where the loss of continuity stems from, If it is a simple case of a loosed connection this will be remedied, If it is discovered that more labour and materials are required, this will be discussed with you prior to any further works being undertaken and a full explanation of the findings demonstrated.

To address observation 7.

Supply and installation of a switched fused spur for the boiler.

To address observation 12.

Supply and installation of appropriate circuit breaker.

To address Observation 13.

Supply and installation of correctly sized main earth cable.

Hrs/Qty	Service	Rate/Price	Adjust	Sub Total
1	Materials and Labour. Cost to supply materials and labour to install them to complete works as described above.	£987.64	0%	£987.64
1	Testing and certification as required to comply with Part P of the building regulation including notification to your local authority. Included as part of our service.	£0.00	0.00%	£0.00

Sub Total	£987.64
VAT Not Applicable	£0.00
Paid	-£250.00
Total Due	**£737.64**

Thanks for choosing Hiskins Electrical Services | Commercial & Domestic Electricians
Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT

Payment is due upon completion. Late payment is subject to fees of 5% per day. Payment should be made to Account Number 28726012, Sort Code 070806, Account Name Karl Atkins