

Hiskins Electrical Services

01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:

Hiskins Electrical Services

Holly Lane, Barwell, Leicestershire, LE9 8BT

Enquiries@HiskinsElectrical.co.uk

Quote
Number

QUO-3459

Quote Date

26th September
2024

Valid Until

26th October 2024

Total

£6,625.34

To:

AW Technology David Haigh

West Street, Earl Shilton, LE9 7EJ

DHaigh@AWTechnology.com

Quotation for remedial works at AW Technology new premises as follows-

Incoming Supply

Supply and installation of Type 1 surge protection device.

DB1

1 hour of labour to investigate observation 1, Zdb at DB1 is higher than would be expected

Supply and installation of RCBO for DB1 lighting circuit.

Supply and installation of RCBO for DB1 socket circuits rated up to 32A.

Supply and installation of correct circuit breaker DB1 circuit 1L1.

Supply and installation of 2 new metal clad sockets and back boxes DB1 circuit 1L1.

Supply and installation of 1 new metal clad socket, DB1 Circuit 2L2.

2 hours of labour to investigate observation 7, DB3 circuit 4L2, No continuity of ring final circuit.

Supply and installation of replacement EML test switch.

Supply and installation of correct cable type for exterior lights.

Rectification of Hole in DB1, Condition of enclosure(s) in terms of IP rating.


re-labelling of circuit as required and addition of RCD test notice.

DB2

Thanks for choosing [Hiskins Electrical Services](#) | Commercial & Domestic Electricians

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT

For our full service terms and conditions please visit www.hiskinselectrical.co.uk



Hiskins Electrical Services


01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Supply and installation of correct circuit breaker DB2 3L2,
Supply and installation of correct circuit breaker DB3 1L1.
Supply and installation of RCBO for DB2 lighting circuits x 7.
DB3,
Supply and installation of replacement distribution board.
Supply and installation of switched fused spur, observation 31.
2 hour of labour to investigate observation 32, DB1 Circuit 2L2, high R2 value measured.
2 hours of labour to investigate observation 33, DB2 Circuit 2L3, low R2 value measured.
2 hours of labour to investigate observation 34. DB2 Circuit 6L2, High ELI value measured.
2 hours of labour to investigate observation 35 DB3 Circuit 4L2, No continuity of any of the 3 conductors in the Ring Final circuit.

Hrs/Qty	Service	Rate/Price	Sub Total
1	Materials and Labour. Cost to supply materials and labour to install them to complete works as described above.	£6,625.34	£6,625.34
1	Testing and certification as required to comply with Part P of the building regulation including notification to your local authority. Included as part of our service.	£0.00	£0.00
		Sub Total	£6,625.34
		VAT Not Applicable	£0.00
		Total	£6,625.34

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Napit. Our membership with Napit allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.



Hiskins Electrical Services

01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

On acceptance of this quote a 25% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Sort Code 070806 Ac No. 28726012.

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT