

Hiskins Electrical Services

01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:

[Hiskins Electrical Services](#)

Holly Lane, Barwell, Leicestershire, LE9 8BT

Enquiries@HiskinsElectrical.co.uk

Quote
Number

QUO-3612

Quote Date

12th February
2026

Valid Until

14th March 2026

Total

£5,215.58

To:

Becky Shearing

47 Stoneygate Drive, Hinckley, LE10 1TB

Becky.Shearing2976@Yahoo.com

Quotation for electrical works at 47 Stoneygate Drive as detailed below.




Hiskins Electrical Services

01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Power Circuits Materials and Labour. Supply and installation of twin walled power ducting as shown in plan. Supply and installation of new power cable from property incoming supply to summer house. Supply and installation of new supply tails from incoming supply to new consumer unit within main house. Supply and installation of new earthing conductor from incoming supply to new consumer unit within main house. Supply and installation of Henley blocks to split supply and allow installation of the new supply tails. Supply and installation in main house of 18th edition metal clad consumer unit with surge protection and time delayed residual current protection. Supply and installation in summer house of 18th edition metal clad consumer with RCBO's for all new circuits required for garden electrics. Supply and installation of 20A 2.5mm power cable for all pond pumps, water features and heaters. Supply and installation of 130 meters of 3 core switching cable to each water feature and each pond pump. Supply and installation of 6 IP65 fused isolators at each pond pump and each water feature to provide local isolation and allow connection to power supply safely. Supply and installation of switching panel in conservatory, this will include installation of 2, 3 core and earth cables to manage switching of the water features and pond pumps.	£3,419.24	£3,419.24



Hiskins Electrical Services


01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Lighting Circuits Materials and Labour. Supply and installation of 10A 1.5mm power cable from summer house to conservatory to accommodate all required garden lighting. Supply and installation of 12v LED strip tape and drivers to steps from conservatory to garden and end of alley from front of house to entrance of garden. Supply and installation of 120m of 4 core switching cable to each lighting position (2 at Pagoda1, 2 at Pagoda 2, existing plant lights, 2, steps lights. Supply and installation of 2, 3 core and earth cables to manage switching of each area of lighting from within conservatory. Supply and installation 4 IP65 switches x 4, 2 at each Pagoda. Supply and installation of 2 exterior sensor lights	£1,796.34	£1,796.34
1	Testing and certification as required to comply with Part P of the building regulation including notification to your local authority. Included as part of our service.	£0.00	£0.00
		Sub Total	£5,215.58
		VAT Not Applicable	£0.00
		Total	£5,215.58

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Napit. Our membership with Napit allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.

On acceptance of this quote a 50% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Account name Karl Atkins, Sort Code 070806, Ac No. 28726012.



Hiskins Electrical Services

01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT