Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

Quote Number	QUO-3238
Quote Date	10th February 2022
Valid Until	12th March 2022
Total	**£2,396.54**

To:
Mr And Mrs Bennion
4 Glebe Road, Hinckley
John.Bennion@ntlworld.com

Full rewire of property.

Supply of required cabling to provide the following circuits and accessories to conform with current wiring regulation as described in BSEN7671:2018 as amended.

Living room

5 Double sockets in white.

2 Pendant light's with switches in white

1 Smoke Alarm

Kitchen

4 Double sockets in white.

2 Pendant light's with switches in white.

1 Heat alarm

Entrance

1 pendant light with 2 gang switch in white.

Top of stairs

1 pendant light with 2 gang switches in white

1 Smoke alarm

1 Double socket in white

Front bedroom

2 Double sockets in white.

1 pendant light with switch in white.

Rear bedroom

1 Double sockets in white.

1 pendant light with switch in white.

Box bedroom

1 Double socket in white.

1 Pendant light with switch in white.

Bathroom

1 Shower circuit to existing shower.

1 Batten light holder and pull cord switch in white.

Exterior

1 Sensor light to side of property.

1 switched light to front of property.

Hrs/Qty	Service	Rate/Price	Sub Total
1	Materials and Labour Cost of materials and labour to complete the work as listed above.	£1,997.12	£1,997.12

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Testing and certification as required for PartP of the building regulations and notification to Hinckley and Bosworth Borough Council. Included as part of our price.	£0.00	£0.00

Sub Total	£1,997.12
VAT Not Applicable	£399.42
Total	**£2,396.54**