Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

Quote Number	QUO-3471
Quote Date	11th October 2024
Valid Until	10th November 2024
Total	**£1,543.86**

To:
Mr & Mrs Hickman
3 Jefferies Close, Hinckley, LE10 1QS
MHickman14@Sky.Com

Quotation for electrical works at 3 Jefferies Close as follows:-

Supply and installation of replacement consumer unit, this will be an 18th edition wiring regulations consumer unit with RCD protection for all circuits and surge protection devices as required to comply with BS7671 and PartP of the building regulations.

Supply and installation of upgraded supply cables from the meter as required.

Supply and installation of upgraded Main earthing cable from incoming supply service head as required.

Supply and installation of 10mm bonding cables to gas service pipe as required by BSEN7671.

Supply and installation of 10mm bonding cables to water service pipe as required by BSEN7671.

A full test of the electrical installation will also be carried out as part of this piece of work and certification as required to comply with Part P of the building regulation including notification to your local authority.

2 Hours of labour to troubleshoot and locate faulty sockets that are currently not working. Troubleshoot glowing light in bedroom.

Removal of wall light in living room.

Removal of existing light fitting in area outside kitchen, supply and installation of replacement pendant type light fitting.

Supply and installation of replacement socket to main bedroom underneath window, the new

socket will be flush mounted and changed to a double.

Removal of existing light fitting in living room and installation of client supplied replacement.

Supply and installation of 5, 1 gang light switches.

Disconnect pump from socket in second bedroom.

Hrs/Qty	Service	Rate/Price	Sub Total
1	Materials and Labour. Cost to supply materials and labour to install them to complete works as described above.	£1,543.86	£1,543.86
1	Testing and certification as required to comply with Part P of the building regulation including notification to your local authority. Included as part of our service.	£0.00	£0.00

Sub Total	£1,543.86
VAT Not Applicable	£0.00
Total	**£1,543.86**

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Napit. Our membership with Napit allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.

On acceptance of this quote a 25% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Sort Code 070806 Ac No. 28726012.

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT