Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

Quote Number	QUO-3469
Quote Date	4th October 2024
Valid Until	3rd November 2024
Total	**£3,688.21**

To:
Hinckley Sea Cadets - Nicola Anstee
The Wharf, Coventry Road, Hinckley, LE10 0NQ
Hinckley-Sea-Cadets@outlook.com

Quotation for EICR remedial works and required further investigations as follows-

Observations 1&2 - Supply and installation of replacement time delayed Residual Current Device.
Observation 4 - Supply and installation of replacement circuit breaker.
Observation 5 - 2 hour to further investigate high ELI reading.
Observation 6 - 2 hour to further investigate lack of continuity of circuit protective conductor.
Observation 7 - 2 hour to further investigate lack of continuity of neutral conductor.
Observation 8 - 2 hour to further investigate high ELI reading.
Observation 9 - 2 hour to further investigate additional cables attached to DB2.
Observation 10 - Supply and installation of blanking plates.
Observation 13 - 2 hour further investigation of additional conductors and re-termination of conductors to end point.
Observation 14 - 2 hour further investigation of additional conductors.
Observation 15 - 2 hour further investigation of additional conductors.
Observation 16 - supply and installation of correct cartridge fuse.
Observation 17 - 2 hour further investigation of additional conductors.
Observation 18 - 2 hour to further investigate high ELI reading.
Observation 21 - Supply and installation of bonding conductor to incoming gas service pipe.
Observation 22 - 3 hour further investigation to identify end points and re test.
Observation 23 - Supply and installation of replacement circuit breaker.

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Materials and Labour. Cost to supply materials and labour to install them to complete works as described above.	£3,688.21	£3,688.21
1	Testing and certification as required to comply with Part P of the building regulation including notification to your local authority. Included as part of our service.	£0.00	£0.00

Sub Total	£3,688.21
VAT Not Applicable	£0.00
Total	**£3,688.21**

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Napit. Our membership with Napit allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.

On acceptance of this quote a 25% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Sort Code 070806 Ac No. 28726012.

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT