**Hiskins Electrical Services**
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

# Quote

**From:**
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

| | |
|---|---|
| Quote Number | QUO-2905 |
| Quote Date | 4th July 2019 |
| Valid Until | 2nd September 2019 |
| **Total** | **£852.00** |

**To:**
Linda Cooper
34 Pallet Drive, Nuneaton CV11 6LT
07967367248
Linda01Cooper@hotmail.co.uk

During my visit to you property today the following observations were made, as discussed despite these observation being about the current installation not meeting some of the current regulations there is no lawful obligation on your part to bring the installation up to current standards.

| Hrs/Qty | Service | Rate/Price | Sub Total |
|---|---|---|---|
| 1 | Upgrade of current fuse board to current 18th edition regulations Consumer Unit<br>1. Current fuse board does not provide RCD protection of circuits.<br>2. Bonding of extraneous conductive parts both not present for one service and under sized for another.<br>3. Circuits not separated adequately. | £500.00 | £500.00 |
| 1 | Upgrade of bonding to extraneous conductive parts and installation of bonding where missing<br>The purpose of earthing is to provide a path for electric fault current to flow safely to earth to enable the circuit breaker or fuse to operate. Bonding is the connection of the incoming metal gas and water pipes to the main installation earthing terminal and is vital for your protection from electric shock. | £150.00 | £150.00 |

**Hiskins Electrical Services**
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

# Quote

| Hrs/Qty | Service | Rate/Price | Sub Total |
|---|---|---|---|
| 1 | Upgrade of meter tails<br>Your current meter tails are 16mm, when a new consumer unit is installed it is require by current regulations to upgrade these to 25mm. | £60.00 | £60.00 |
| 1 | Separation of circuits<br>The installation of a new consumer unit will allow for the separation of some of the existing circuits how ever without further work within the property it self, not all circuits will be separated. The installation of the new consumer unit will be a huge leap forward in bringing the electrical safety of the property closes to current regulations. | £0.00 | £0.00 |

| | |
|---|---|
| Sub Total | £710.00 |
| VAT Not Applicable | £142.00 |
| **Total** | **£852.00** |

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Stroma. Our membership with Stroma allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.

On acceptance of this quote a 25% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Sort Code 090129 Ac No. 31668172.