Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

From:
Hiskins Electrical Services
Holly Lane, Barwell, Leicestershire, LE9 8BT
Enquiries@HiskinsElectrical.co.uk

Quote Number	QUO-3434
Quote Date	25th May 2024
Valid Until	24th June 2024
Total	**£3,290.00**

To:
Silvan Floors
Saw Mill, Thurlaston, Enderby Rd, Thurlaston,
Leicester LE9 7TF
Richard@SilvanFloors.com

Hrs/Qty	Service	Rate/Price	Sub Total
1	Observation 4 DB1 Circuits 4L3 Incorrect selection of circuit protective device for circuit supplying lighting. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (433.1; 533.2.1)	£60.00	£60.00
1	Observation 5 DB1 Circuit 4L2, unidentified end point. (514.8.1; 514.9.1)	£160.00	£160.00
1	Observation 6 DB1 Circuit 4L3, no residual current protection. (411.4.204; 411.5.2; 531.2) (411.3.3; 415.1)	£150.00	£150.00
1	Observation 8 Junction box in press room has no cover and singularly insulated cables are exposed. (526.8) (526.5) (522.8.5)	£60.00	£60.00
1	Observatin 9 Incorrect selection of circuit protective device for circuit supplying lighting in press room (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (433.1; 533.2.1)	£60.00	£60.00
1	Observation 10 DB1a supplied directly from incoming supply without overload protection. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433)	£350.00	£350.00
1	Observation 11, 14 and 21 IP rating of DB1 is insufficient. (416.2)	£80.00	£80.00

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Observation 17 DB2 Circuit 3L1, no residual current protection. (411.4.204; 411.5.2; 531.2) (411.3.3; 415.1)	£150.00	£150.00
1	Observation 18 DB2 Circuit 3L2, no residual current protection. (411.4.204; 411.5.2; 531.2) (411.3.3; 415.1)	£150.00	£150.00
1	Observation 19 DB2 Circuit 7L1, no residual current protection. (411.4.204; 411.5.2; 531.2) (411.3.3; 415.1)	£150.00	£150.00
1	Observation 20 DB2 Circuit 9L1-9L3, additional cables attached to circuit. (514.8.1; 514.9.1)	£160.00	£160.00
1	Observation 24 DB2 Circuit 3L1, socket with insufficient IP rating. (416.2)	£90.00	£90.00
1	Observation 26 Db1 Circuit 3L1 has additional cables attached. (514.8.1; 514.9.1)	£160.00	£160.00
1	Observation 27 DB1 Circuit 1L1-1L3, Selection of protective device for installed cables is unsuitable. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£160.00	£160.00
1	Observation 27a DB1 Circuit 6L1-6L3, Selection of protective device for installed cables is unsuitable. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£160.00	£160.00
1	Observation 28 DB1 Circuit 11L1-11L3, additional cables attached. (514.8.1; 514.9.1)	£160.00	£160.00
1	Observation 29 DB1 Circuit 12L1-12L3, Selection of protective device for installed cables is unsuitable. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£150.00	£150.00

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Hrs/Qty	Service	Rate/Price	Sub Total
1	Observation 31 DB2 Circuit 4L3, R1+R2 is higher than permitted by BSEN7671. (411.4.201) (411 .3.2.2)	£80.00	£80.00
1	Observation 32 DB2 Circuit 12L1-12L3, Selection of protective device for installed cables is unsuitable. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£150.00	£150.00
1	Observation 33 DB1a Circuit 1L1-1L3, Selection of protective device for installed cables is unsuitable. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£150.00	£150.00
1	Observation 34 DB1a Circuit 1L1-1L3, selection of cable (SY Cable) used in this circuit does not comply with BSEN7671. (Section 523)	£160.00	£160.00
1	Observation 35 DB1a Circuit 2L1-2L3, selection of cable (SY Cable) used in this circuit does not comply with BSEN7671. (Section 523)	£160.00	£160.00
1	Observation 36 DB2a Circuit 1L1-1L3, co-ordination between circuit protective conductor and cable sizes may not comply with BSEN7671, further testing required with isolation of circuit and shut down of attached machinery. (411.3.2; 411.4; 411.5; 411.6; Sections 432, 433) (Section 523) (433.1; 533.2.1)	£80.00	£80.00
1	Observation 37 Light switch at entrance to factory is not attached to back box, live connections exposed. (526.8) (526.5) (522.8.5)	£0.00	£0.00
1	Observation 38 Light in bathroom is not correctly closed, live connections exposed. (526.8) (526.5) (522.8.5)	£100.00	£100.00

Hiskins Electrical Services
01455 360 370 - 07455 640640
Commercial & Domestic Electricians

Quote

Sub Total	£3,290.00
VAT Not Applicable	£0.00
Total	**£3,290.00**

All our work is covered by our 6 year guarantee which is backed by our government approved competent persons scheme Napit. Our membership with Napit allows us to certify all works carried out with local building regulations as required by law for PartP of the building regulations.

On acceptance of this quote a 25% deposit is required to cover materials and secure time in our schedule to carry out your work. Deposits can be paid via bank transfer to Sort Code 070806 Ac No. 28726012.

Please Note Hiskins Electrical Services is not a VAT registered business and as such you will not be charged extra for VAT